

8

**OFFICE OF THE PRINCIPAL
WOMEN'S TRAINING COLLEGE
NORTH GANDHI MAIDAN
PATNA 800001**

Phone No 0612-2218809, Web site: wtcpu.org.in
EMERGENT NOTICE INVITING QUOTATION

Quotation No: 01/NH/2025

Date: 23.06.2025

NAME OF WORK: ROOF TREATMENT OF EASTERN PORTION OF ROOF OF WOMEN'S TRAINING COLLEGE, P.U. PATNA

Sealed quotations are invited in prescribed format for this work. For details terms and condition , please visit the office of the undersigned on any working days from 10.30 A.M. to 5.00 P.M.

Designation of officer inviting quotation	Principal, Women's Training College, Patna
Place, Time & Date of receiving of quotation	Office of the Principal, Women's Training College, Patna up to 3.00 p.m. on 01.07.2025
Place, Time & Date of opening of quotation	Office of the Principal, Women's Training College, Patna at 3.30 p.m. on 01.07.2025

PRESCRIBED FORMAT

S.N.	Description	Quantity	Unit	Rate	Amount (Rs.)
1	Providing skilled labours for cleaning un wanted plants etc. grown over roof and cleaning and brooming the roof for necessary works as per direction of Engineer-in-charge.	1	Day	Day	
2	15 mm cement plaster on rough side of single or half brick wall of mix.1:4(1 cement: 4 coarse sand)	20	Sqm	Sqm	
3	Providing and laying APP (Atactic Polypropylene Polymer) modified prefabricated five layer 3 mm thick water proofing membrane, black finished reinforced with non-woven polyester matt consisting of a coat of bitumen primer for bitumen membrane @ 0.40 litre/ sqm by the same membrane manufacture of density at 25°C, 0.87-0.89 kg/ litre and viscosity 70-160 cps. Over the primer coat the layer of membrane shall be laid using Butane Torch and sealing all joints etc., and preparing the surface complete. The vital physical and chemical parameters of the membrane shall be as under : Joint strength in longitudinal and transverse direction at 23°C as 650/450N/5 cm. Tear strength in longitudinal and transverse direction as 300/250N. Softening point of membrane not less than 150°C. Cold flexibility shall be upto - 2°C when tested in accordance with ASTM, D - 5147. The laying of membrane shall be got done through the authorised applicator of the manufacturer of membrane.3 mm thick.	429	Sqm	Sqm	
4	Providing and fixing on wall face unplasticised-PVC(working pressure 4 kgf per sqm) rain water pipes conforming to IS :4985 including jointing with seal ring conforming to IS: 5382 leaving 10 mm gap for thermal expansion. 110 mm diameter	10	m	m	
5	Providing and fixing on wall face unplasticised -PVC molded fittings/accessories for unplasticised-PVC rain water pipes conforming to (S:4985 including jointing with seal ring conforming to IS: 5382 leaving 10 mm gap for thermal expansion.110 mm bend	3	No	Each	
6	Carriage of materials: Sone sand from Koelwar, 45 Km distance of surface road.	0.4	Cum	Cum	
7	Price difference of materials for Patna urban area: Cement.	3	Bag	Bag	
8	Reserved price for any other un seen work.	1	L.S.	L.S.	4838
Total Amount					

Terms and conditions:

- 1 Papers to be submitted with quotation: Copies of Registration Certificate, G.S.T. Certificate, PAN , Experience, etc.
- 2 At the time of opening of quotation only participants or his single authorised representatives with authority letter will be allowed to present.
- 3 Work must be completed within 1 month after issuance of work order.
- 4 Rate of serial number 8 has been fixed as Rs4838.
- 5 Any registered agency of Government of Bihar / C.P.W.D. /M.E.S. will be considered.
- 6 Payment will be considered after satisfactory completion of work and after submitting satisfactory work completion certificate.
- 7 All disputes, what so ever shall be referred to the sole arbitration of the Principal, Women's Training College, Patna and his decision shall be final and binding on the agency.
- 8 The undersigned reserves the right to accept or reject any or all the quotation without assigning any reasons.

Lipika
PRINCIPAL
WOMEN'S TRAINING COLLEGE
PATNA

P.K.A.
13/08/25

PRINCIPAL
WOMEN'S TRAINING COLLEGE
PATNA